

PORT OF PORTLAND FUTURE CONSTRUCTION CONTRACTS

October – December 2020

PORTLAND INTERNATIONAL AIRPORT

DEICING VAULT REHAB PHASE 2 – Pump Stations G, L, N \$600,000
Perform rehab work on vaults and at deicing plant, and on associated mechanical equipment.

MAINTENANCE BUILDING 7111 HVAC REPLACEMENT \$600,000
Remove and replace existing HVAC units.

CUSTOMS AND BORDER PROTECTION (CBP) IMPROVEMENTS \$100,000
Install electrical conduit and electrical infrastructure for new IT drops, and power receptacles for new workstations.

MARINE TERMINAL 6

BASIN K & L STORMWATER TREATMENT \$2,800,000
Construct stormwater management facility to treat surface runoff in Basins K and L.

PAVEMENT REHABILITATION \$1,500,000
Rehabilitate the T6 Container Yard entrance and exit roads, Berth 607 floating hull pavement, and Honda entrance road.

January – March 2021

PORTLAND INTERNATIONAL AIRPORT

AIR CARGO WAY MULTI-USE PATH \$600,000
Construct a 12-foot wide Multi-Use Path (MUP) on the north side of NE Air Cargo Way. Approximate length of this segment of the MUP is 1,100 feet. Improvements include earthwork, concrete curbing, asphalt paving, storm drain improvements, and signing/stripping.

HILLSBORO AIRPORT

TAXIWAY A REHABILITATION \$13,600,000
Reconstruct nearly the full length of Taxiway A, as well as the connecting Taxiways A6, A8, A9 and a portion of Taxiway B. Improvements include full-depth reconstruction, pavement rehabilitation, and all associated electrical and storm drainage work. Work will be performed in partnership with the FAA and coordinated with Port of Portland Operations.

MARINE TERMINAL 4

T4 ELECTRICAL REPLACEMENTS \$1,000,000
Reroute electric feeder and replace medium-voltage equipment.

T4 BASIN M STORMWATER IMPROVEMENTS \$650,000
Construct stormwater infiltration basin and associated infrastructure.

April – June 2021

PORTLAND INTERNATIONAL AIRPORT

NEW KENNEDY FEEDER

\$3,000,000

Construct the new Kennedy 15 KV electrical feeder from the point-of-service on the NE corner of the intersection of NE 47th Ave and NE Cornfoot Way to a new vault located on the airfield south of Taxiway C and east of Taxiway J.

GLYCOL SPRINKLER SYSTEM REPLACEMENT

\$600,000

Replace five existing glycol sprinkler systems (located at PDX Maintenance loading dock, CCD/CCE pass-through, CCD West pass-through, CCD South exterior canopy near gate D8, and CCD North exterior canopy near gate D9), with new dry sprinkler systems.